

(An autonomous Institute of Dept. of Biotechnology, Ministry of Science & Technology, Govt. of India)
Bioscience cluster 3rd mile stone Faridabad Gurgaon Expressway Faridabad
PHONE No. : 0129-2876421 FAX: 0129-2876 402 Web Site : www.thsti.res.in

NOTICE INVITING QUOTATION

Ref. of NIQ:- THS.E.101.25-26.NIQ/11

Dated: -04/02/2026

Name of work:- Electrical work in newly allotted office space for the Store & Purchase Section near ICICI Bank in THSTI Building at NCR Biotech Science Cluster Faridabad.

Sealed quotations are invited on behalf of the Executive Director, THSTI from reputed firms/ agencies/ contractor/ for the of work of 'Electrical work in newly allotted office space for the Store & Purchase Section near ICICI Bank in THSTI Building at NCR Biotech Science Cluster Faridabad' as per enclosed schedule of work and terms & conditions submitted up to 10/02/2026, 2.00 PM in sealed cover in the office of Engineer, THSTI. The quotation will be opened on the same day at 2:30 PM in the presence of intending bidders if any. The schedule of work and terms & conditions given below: -

Terms & conditions: -

1. The work shall be carried out as per direction & recommendation of the Engineer-In-Charge.
2. The rates are Net inclusive of all taxes; duties etc. and nothing Extra shall be paid.
3. Income Tax etc. will be deducted as applicable on the value of work done.
4. The deviation limit shall be $\pm 10\%$.
5. The contractor is required to follow all labour laws, Minimum Wages Act and other provision to labour welfare applicable from time to time. Nothing extra shall be paid for the same.
6. The work shall be executed without any loss/damage to THSTI properties etc.
7. The total work Included: -
 - I. Supply, Installation, Termination & Testing of electrical system as per Govt. guidelines.
 - II. Testing of the electrical system should be done by the agency.
8. Any damages occur during the execution of work, the same should be rectified by the contractors on their own cost.
9. Contractor shall be fully responsible for safety of his workers and in case of any misshaping the entire responsibility shall be on the contractor.
10. The Contractor shall clean the site after completion of work in all.
11. The dismantled material shall be returned to THSTI if any.
12. The time of completion of the said work at THSTI is 10 days from the date of Issue of Work Order from the office.
13. Liquidated damages shall be lived on the Contractor @1% per week of delay to the maximum up to 10% of the contract value after expiry of completion period as stipulated in NIQ

14. The rates are inclusive of 1 Year warranty period.
15. Terms of Payment: 90 % of Contract Value after submission original invoice, Completion certificate, Delivery challan and test report if any against the Work.
16. 10% Security deposit on work done value shall be deducted from the bill which shall be refunded as below after satisfactory completion of work of warrantee period i.e. 1 Year.

Note: - The agency should quote their rate in their original letter head along with signature & seal of agency.

Thanking You,

Yours faithfully

Contractor sign with Seal

Engineer (IEE)

Bill of Quantity

Name of work-: Electrical work in newly allotted office space for the Store & Purchase Section near ICICI Bank in THSTI Building at NCR Biotech Science Cluster Faridabad

S.N.	Description of item	Quantity	Unit	Rate	Amount
1.	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
I.	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	90	Metre		
II.	2 x 4 sq.mm. + 1 x 4 sq.mm. earth wire	120	Metre		
III	4 X 10 sq. mm + 2 X 6 sq. mm earth wire	25	Meter		
2	Supplying and fixing following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc as required.				
I.	3 Module (100mm x 75mm)	18	Each		
II.	6 Module (200mm x 75mm)	16	Each		
III	8 Module (125mmX125mm)	5	Each		
3	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
I.	5/6 amps switch	18	Each		
II.	15/16 amp switch	44	Each		
III.	3 pin 5/6 amp socket outlet	18	Each		
IV.	6 pin 15/16 amp socket outlet	44	Each		
V.	Telephone socket outlet	5	Each		
4	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmoured telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
I.	2 Pair	100	Metre		
II.	20 Pair	80	Metre		

5	Supplying, installation, Testing & Commissioning of Panel light 2x2 ft., of following body material and construction as per IS : 10322 with driver as per the requirement				
I	36 watt	18	Each		
6	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).				
I	4 way (4 + 12), Double door	1	Each		
7	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
I	Single pole	12	Each		
8	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
I	63 A	1	Each		
	Total				
	Taxes				
	Total (Inclusive of all taxes)				

[

]

Technical Specification

Make & Specification

1. Wire & accessories: -

- a. Make/ Model: -
- b. Specification Detail: -
- c. Catalogue if any: -

2. MCB & Distribution box & accessories: -

- a. Make/ Model: -
- b. Specification Detail: -

3. Other -

- a. Make/ Model: -
- b. Specification Detail: -

Signature of tenderer with Seal & Date

CERTIFICATE FOR SITE INSPECTION

Certified that we..... (Name of agency) have visited the site on dated..... and assessed the nature and amount of work involved before submitting our offer. We will be able to complete the works within the stipulated time and also certified that we will be able to supply the material/executing the work as per specification to suit the site conditions.

**Address of site: - THSTI Project Site Civil Hospital Gurgaon under THSTI, NCR-Biotech Science Cluster at THSTI 3rd mile stone Faridabad Gurgaon Expressway
Faridabad Haryana-121001**

**ENGINEER IN- CHARGE,
THSTI**

Signature of tenderer with Seal & Date

Annexure-3

The tenderer provides the following detail along with their quote/bid:-

Details of Firm

1. Name of the Firm / Company:
2. Registered Address:
3. Address for Communication:
4. Contact Information
5. Office Phone Number:
6. Residence Phone Number:
7. Mobile Number:
8. Fax:
9. E-Mail:
10. The detail of electrical licence (Copy attached)
10. Status of the Firm:

(Please tick appropriate box & attach proof)

Company

Partners

Year of Establishment:

Registration Details

Companies / Firm Registration Number & Date:

Income Tax PAN No.:

Goods & Service Tax No.:

(attach proof)

Signature of tenderer with Seal & Date

Annexure-4

Detail of similar work experience

[illegible]

Undertaking for non-blacklisting

Sub: Declaration for non-blacklisting

Reference No: _____

Dear Sir,

We hereby declare that we are not blacklisted by any Central/ State Government/ agency of Central/ State Government of India or any other country in the world/ Public Sector Undertaking/ any Regulatory Authorities in India or any other country in the world for any kind of fraudulent activities.

Yours Faithfully,

(Signature of the Bidder, with Official Seal)

Valid Electrical Contractor Licence